



JETTY CREEK DIVERSION AND STREAM RESTORATION IMPROVEMENTS PROJECT

Addendum No. 1

January 31, 2017

The following updates, clarifications and additions are hereby made a part of the Contract Documents for the Jetty Creek Diversion and Stream Restoration Improvements Project as fully and completely as if the same were fully set forth herein and must be acknowledged in the Proposal. Addendum must be acknowledged in the Proposal by the Contractor.

REPLACE

1. Impoundment Liner:

All References to the bedding for the liner shall be changed from 2" thick sand to 6" thick sand in the plans and technical specifications.

CLARIFICATIONS

The following are clarifications:

1. Impoundment Liner:

The liner shall be installed on top of the proposed retaining wall. The liner shall be anchored to the soil per manufacturer recommendations, with proper protection from the retaining wall, and fill in voids in the retaining wall as recommended by the manufacturer.

The geotextile membrane shall contain stiffeners (sometimes referred to as batten bars) and retaining wall backfill as designed and required by manufacturer to make the product adhere and perform properly in a nearly vertical orientation. The cost of this design shall be included in the price shown in the bid book.

2. Drawing Contours:

The proposed contours shown on the plans are 1 ft. contours. Quantity take-offs have been performed and are shown on the proposal form. These quantities should be used for estimating. The existing contours shown are from the original survey many years ago, so they should not be used for estimating quantities. They are only shown for general reference. Another survey was performed more recently, to more closely estimate quantities, but it was beyond the scope of this project to update the plans to match the survey. It is not anticipated to be significantly different as a reference, but the old survey is not considered accurate enough for quantity take-offs.

I acknowledge I have received Addendum No. 1 for the Jetty Creek Diversion and Stream Restoration Improvements Project.

Signature of contractor/authorized representative

Date